F.H.W.A. REGION	STATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS	AS BUILT
9	AZ	61244122	1	1	

= Direction of Traffic Flow

GOLDMINE GULCH TRL

WAGON WHEEL RD

SKYLINE DR

EXISTING FENCE

CULVERTS AT DRAINAGE CROSSINGS TYPICAL

100.0'

EXISTING PARKING

36'

24'

18'

40'X80' RV SPACE

40'X80' RV SPACE

18'

30'

Van-Accessible

ENTRY & RESTROOM

24'

18'

SHADE & PICNIC TABLE

SHADE & PICNIC TABLE

SHADE & PICNIC TABLE

18' 18' 18' 18' 18' 18' 18' 18'

24'

30'

18'

18'

RESTROOM

GOLDMINE TRAIL

PARKING SPACES		
Vehicle Type / Use	Size	Number of Spaces
Standard Parking Space (Passenger Car – AASHTO Design Vehicle)	10' X 20'	125
Crew Cab Dual Rear Wheel Truck & 42' 6-Horse Gooseneck Trailer	18' X 80'	5
Crew Cab Single Rear Wheel Truck & 23' 4-Horse Bumper-Pull Trailer	18' X 60'	3
ADA Standard Accessible Parking Spaces	11' X 20' With 5' Wide Access Aisle	4
ADA Van-Accessible Parking Spaces	11' X 20' With 8' Wide Access Aisle	1

40 0 40 80 120

Horiz. Scale: 1" = 40'
(Contour Interval = 2')

PRELIMINARY DESIGN

10%

NOT FOR CONSTRUCTION

DRAWING NO: P1

PINAL COUNTY DEPARTMENT OF PUBLIC WORKS
ENGINEERING BRANCH

	NAME	DATE
DESIGN	JFK/BLF	5/16
DRAWN	BLF	5/16
CHECKED	JFK/LR	5/16

Proposed Parking Layout [5-13-2016]

LOCATION

San Tan Mountain Regional Park – GoldmineTrailhead Parking